PART 1 – GENERAL

1.1 SUMMARY:

A. WORK INCLUDES:

- 1. SnoCleat aluminum snow guard that attaches directly to the roof deck.
- 2. Coordinate with the installation of the metal roofing system to assure the proper fastening of the metal roof to the substructure.
- 3. Provide all necessary components: Mill Finish, Brackets, Bars, and Tek Screws

B. RELATED SECTIONS:

- 1. Master Format™ 2004 Section 07 41 13: Preformed Metal Roofing
- 2. Master FormatTM 2004 Section 07 60 00: Flashing and Sheet Metal
- 3. Master FormatTM 2004 Section 07 40 00: Metal Roof Panels
- 4. Master Format™ 2004 Section 07 61 01: Sheet Metal Roofing

1.2 SYSTEM DESCRIPTION:

A. COMPONENTS:

- 1. SnoCleat System consisting of extruded 6063-T5 aluminum SnoCleat and Brackets.
- 2. Fasteners
 - a. Non Floating Mechanically Fastened Metal Roofs: Attach with (4) #14 non corrosive screws and butyl tape.

B. DESIGN REQUIREMENTS:

- 1. Snow Guard Layout(s) showing snow guard spacing and location, roof dimensions and ground snow load.
- 2. Based on snow load, climatic conditions, length of roof panel and width of panel; multiple rows of SnoCleat may be needed.
- 3. Cut sheets with descriptions of product(s) and installation instructions.
- 1.3 SUBMITTAL: Submit Manufacturer's specifications, standard detail drawings and installation instructions.
- 1.4 QUALITY ASSURANCE: Installer to be experienced in the installation of metal roofing and snow retention systems for a period of not less than 5 years in the area of the project.
- 1.5 DELIVERY/STORAGE/HANDLING: Inspect material upon delivery and order replacements for any missing or defective items. Keep material dry, covered and off the ground until installed.

PART 2 – PRODUCTS

2.1 MANUFACTURER:

| ACTION MIANUTACTURING, LAX | Action | Manufacturing, | LLC |
|----------------------------|--------|----------------|-----|
|----------------------------|--------|----------------|-----|

| Exclusively Distributed by | Phone: | Fax: | Online: | Warehouse: |
|----------------------------|----------------|----------------|------------------------|-------------------|
| IceBlox, Inc. d.b.a. | (800) 766-5291 | (800) 634-7906 | www.snoblox-snojax.com | 671 Willow Street |
| Snoblox-Snojax | (717) 737-4398 | (717) 697-6141 | support@snojax.com | Lemoyne, PA 17043 |

2.2 MATERIALS:

- A. SnoCleat: Specify an extruded 6063-T5 aluminum SnoCleat in mill finish.
- B. Bracket: Extruded 6063 T5 Aluminum
- 2.3 FINISH:
 - A. Mill Finish

PART 3 - EXECUTION:

3.1 EXAMINATION:

A. Substrate: Inspect roof system to be properly attached and installed to withstand additional loadings incurred.
Notify General Contractor of any deficiencies before installing SnoCleat.

3.2 INSTALLATION:

- A. Comply with architectural drawings for location and with Manufacturer's instructions for assembly and installation.
- B. Clamps must be used at every roof seam in staggered rows.
- C. All Set Screws torqued to 90 in/lbs. and rechecked annually
- D. All top mount bolts torqued to 100 in/lbs. and rechecked annually
- E. Refer to manufacturer's installation instructions

3.3 WARRANTY

A. SnoCleat systems shall include free limited lifetime warranty on parts and finish for all systems following manufacturer's spacing/ installation recommendations.